



NEW STUD WALLS [K10:115] TAKEN SCREED TO UNDERSIDE OF ROOF

new cupboard below display cabinet door frame to allow access to duct (see drawing AA(3)48)

Benching to be removed
Benching to be removed

remove door and block up doorway with blockwork [F10:351] including plaster [M20:210] to both sides

ROOMS 81 & 82 COMBINED INTO 80
REMOVE BLOCKWORK WALLS, INSERT 305x127x48KG UB STEEL SUPPORT BEAM [G12:210] (SPliced AS STRUCTURAL ENGINEER'S DETAIL). BEAM TO HAVE MINIMUM 100MM END BEARING ON 440(L)x215(D)x100(W) CONCRETE PADSTONES WITH M12 RAG BOLTS. ENCASE STEEL IN 2NO LAYERS 12.5MM PLASTERBOARD AND SKIM WITH STAGGERED JOINTS AND MAKE GOOD GENERALLY.

Sheffield Design & Property Architects Division
2-10 CARBROOK HALL ROAD SHEFFIELD S9 2DB
Tel. 0114 2736036 Fax. 01142 2736299 Email. admin@sdandp.demon.co.uk
Sheffield Design & Property, Acting Head of Service I G Taylor ARICS

- Do not scale from this drawing
- All dimensions to be checked on site
- Any errors / omissions to be reported immediately
- If in doubt, ask
- No reproduction of this drawing in any form without permission
- Maps are reproduced from Ordnance Survey with permission of HMSO Crown copyright

REV	DATE	REVISIONS	DRAWN	CHECKED	NOTES
A	12-06-02	Alterations to clients request, splashbacks added, display cabinet remains in corridor	KNS	MAS	
B	22-08-02	Working drawing update	KNS	MAS	

DRAWN	CHECKED	NOTES
KNS	MAS	

CLIENT:	Education
SCHEME:	Parkwood High School Refurbishment
TITLE:	Proposed Food Tech Detail Plan

STATUS	Working Drawings	A1
DRAWN	KNS	SCALE 1:50
CHECKED	MAS	DATE 27-05-02
SCHEME NO	AX 165	REV B
DWG NO.	AL(7)43	

PDF - processed with Cutler - evaluation edition www.cutlerpdf.com